

WISCONSIN CONSTRUCTION SPECIFICATION

7. Mobilization and Demobilization

1. SCOPE

The work consists of the mobilization and demobilization of the Contractor's forces and equipment necessary for performing the work required.

2. EQUIPMENT AND MATERIAL

Mobilization shall include:

- All activities and associated costs for transportation of the Contractor's personnel, equipment, and operating supplies to the site;
- Establishment of offices, buildings, and other necessary general facilities for the Contractor's operations at the site
- Premiums paid for performance and payment bonds including coinsurance and reinsurance agreements as applicable
- Construction and maintenance of haul roads and equipment parking areas
- Other job related items

Demobilization shall include:

- All activities and costs for transportation of personnel, equipment, and supplies not utilized in the project from the site
- Disassembly, removal, and site cleanup of offices, buildings, and other facilities assembled on the site.
- Repair of access roads, temporary haul roads, and equipment parking areas leaving the project site in the same or better condition than at the start of the project.
- General cleanup and house keeping needed to restore a neat and orderly project site.

Access to the site, equipment parking, and staging areas are limited to that shown on the drawings or as approved by the technician.